

LIMESTONE CR ROAD YEPPOON						
Stage 3, 4, 5 & 6 - OP WORKS						
BILL OF QUANTITIES			DATE		1/07/2026 REV A	
	Item		Qty.	Unit	Rate	Total
1	ESTABLISHMENT		\$0.00			
	1.1	Site establishment including fencing - Prov only if works do not flow on from Stage 1 & 2	1	Item		\$0.00
2	ROADWORKS		\$0.00			
	2.1	Trim and compact road subgrade	10,761	m ²		\$0.00
	2.2	Supply & Lay Gravel Pavement				
		Road 2 CH670 - CH1215				
		Sub-base 2 Material Type 2.5 min CBR 15 - 100mm Consolidated Depth (including 300mm behind Kerb)	476.9	m ³		\$0.00
		Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	476.9	m ³		\$0.00
		Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	378.7	m ³		\$0.00
		Road 3 CH3.5 - End				
		Sub-base 2 Material Type 2.5 min CBR 15 - 170mm Consolidated Depth (including 300mm behind Kerb)	218.4	m ³		\$0.00
		Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	128.5	m ³		\$0.00
		Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	107.8	m ³		\$0.00
		Road 4 CH 3.5 - CH 232.7				
		Sub-base 2 Material Type 2.5 min CBR 15 - 185mm Consolidated Depth (including 300mm behind Kerb)	382.0	m ³		\$0.00
		Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	206.5	m ³		\$0.00
		Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	168.2	m ³		\$0.00
		Road 5 CH41.13 - END				
		Sub- Base 1 Material Type 2.3 min CBR 45 - 180mm Consolidated Depth	83.4	m ³		\$0.00
		Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	29.33	m ³		\$0.00
		Road 7 CH 73 - End				
		Sub-base 2 Material Type 2.5 min CBR 15 - 170mm Consolidated Depth (including 300mm behind Kerb)	370.6	m ³		\$0.00
		Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	218.0	m ³		\$0.00
		Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	170.8	m ³		\$0.00
	2.3	Sealing				
		Primer seal - 10mm	8,548	m ²		\$0.00
		Road 2 CH670 - CH1215				
		25mm Asphaltic Concrete	167	Tn		\$0.00
		Road 3 CH3.5 - End				
		25mm Asphaltic Concrete	65	Tn		\$0.00
		Road 4 CH 3.5 - CH 232.7				
		25mm Asphaltic Concrete	101	Tn		\$0.00
		Road 5 CH41.13 - END				
		25mm Asphaltic Concrete	18	Tn		\$0.00
		Road 7 CH 73 - End				
		25mm Asphaltic Concrete	102	Tn		\$0.00
	2.4	Construct Kerb & Gutter				
	2.4.1	Type 2 Mountable Kerb and Channel	2,346	m		\$0.00
	2.4.2	Type 4 Semi- Mountable Kerb to Roundabout Island Road 3	43	m		\$0.00
	2.5	Supply & lay compacted sand or similar sub-base course to Driveways				
	2.5.1	Driveway lot 119 - 150mm consolidated depth	7	m ³		\$0.00
	2.5.2	Driveway lot 1707 - 150mm consolidated depth	26	m ³		\$0.00
	2.5.3	Driveway Beside Lot 115 - 150mm consolidated depth	23	m ³		\$0.00
	2.6	Supply & lay Concrete Driveway (including Layback) per CMDG-R-041				
	2.6.1	Driveway Lot 119 - 125mm Reinforced Concrete Driveway	46	m ²		\$0.00
	2.6.2	Driveway Lot 1707 - 125mm Reinforced Concrete Driveway	176	m ²		\$0.00
	2.7	Supply & lay Concrete Driveway (including Layback) per CMDG-R-042				
	2.7.1	Driveway Beside Lot 115 - 175mm Reinforced Concrete Driveway	154	m ²		\$0.00
	2.8	Testing - Arrange for tests & provide reports as per CMDG (Prov. Qty)				
	2.8.1	Subgrade Compaction	1	Item		\$0.00
	2.8.2	Gravel Compaction Base	1	Item		\$0.00
	2.8.3	Gravel Compaction Sub Base	1	Item		\$0.00
	2.8.4	Subgrade CBR	1	Item		\$0.00
	2.9	Remove Temporaty Turning Circle if constructed in Stage 1/2	3	each		\$0.00
3	STORMWATER DRAINAGE		\$0.00			
	3.1	Supply, Excavate, Joint, Lay & Backfill incl compaction testing				
	3.1.1	375mm dia. HDPE	465.8	m		\$0.00
	3.1.2	450mm dia. HDPE	177.6	m		\$0.00
	3.1.3	525mm dia. HDPE	44.7	m		\$0.00
	3.1.4	600mm dia. HDPE	204.0	m		\$0.00
	3.1.6	750mm dia. RCP RRJ 'Class 3'	252.5	m		\$0.00
	3.2	Construct Concrete Pits AUSPEC C223				
	3.2.1	2.4m Lintel Type 'S' - STD CMDG Type A Gully Pit - SAG	6	each		\$0.00
	3.2.2	2.4m Lintel Type 'S' - STD CMDG Type A Gully Pit	30	each		\$0.00
	3.3	Supply & Construct Custom Concrete Pits				
	3.3.1	Custom grated Junction Pit To plan Detail including Structural Design - Pit 4/1, Pit 2/1, Pit 3/1, Pit 6/9 (1100x900)	4	Item		\$0.00
	3.3.2	Custom grated Junction Pit To plan Detail including Structural Design - Pit 2/80, Pit 1/82 (1100x900)	2	Item		\$0.00

		BILL OF QUANTITIES	DATE	1/07/2026 REV A		
		Item	Qty.	Unit	Rate	Total
	3.3.3	Custom grated Junction Pit To plan Detail including Structural Design - Pit 2/9 (1100x1000)	1	Item		\$0.00
	3.4	Supply, Excavate, Install & Backfill Headwall to suit:				
	3.4.1	750mm DIA. RCP (1/1)	1	each		\$0.00
	3.4.2	Twin 750mm DIA RCP (1/9)	1	each		\$0.00
	3.4.3	525mm DIA. HDPE (headwall into Western Basin)	1	each		\$0.00
	3.5	Removal and Dispose of Temporary Headwalls Installed in Stage 1/2	2	Each		\$0.00
	3.5	Outlet Protection	3	each		\$0.00
4		INTERLOT DRAINAGE	\$0.00			
	4.1	Supply, excavate, bed, lay, joint and backfill pipe				
	4.1.1	150mm Dia. uPVC.	45.3	m		\$0.00
	4.1.2	200mm Dia. uPVC.	40.5	m		\$0.00
	4.1.3	225mm Dia. uPVC.	325.4	m		\$0.00
	4.1.4	300mm Dia. uPVC.	55.2	m		\$0.00
		Supply and Install Stormwater Junctions				
	4.2.1	Junctions to IAD pits	25	each		\$0.00
	4.2.2	Supply and Install Kerb Adaptor in accordance with CMDG -R-061	39	each		\$0.00
	4.2.3	Supply and Install 100mm DIA uPVC junction to lot from Kerb Adaptor in Accordance with CMDG-R-061	234	m		\$0.00
	4.3	Supply and Install Pre-Cast IAD Pits				
	4.3.1	Std. Inspection Pit 600 x 600 mm	7	each		\$0.00
	4.3.2	Std. Inspection Pit 600 x 900 mm	12	each		\$0.00
	4.3.3	Std. Inspection Pit 900 x 900 mm	6	each		\$0.00
	4.4	Supply, Excavate, Install & Backfill Headwall to suit:				
	4.4.1	225mm DIA. HDPE (1/15, 1/16)	2	Each		\$0.00
	4.4.1	300mm DIA. HDPE (1/4)	1	Each		\$0.00
	4.5	Concrete Outlet Protection				
	4.5.1	Outlet scour protection	3	item		\$0.00
5		SUBSOIL DRAINAGE	\$0.00			
	5.1	Excavate, supply, bed, lay, joint and backfill pipe				
	5.1.1	100mm Dia. Draincoil: As per Specification incl. filter "sock"	2,346	m		\$0.00
	5.1.2	Subsoil drain flushing points (@ no greater than 50m Intervals)	47	each		\$0.00
6		SEWER RETICULATION	\$0.00			
	6.1	Supply, Excavate, bed, lay, joint & backfill incl compaction testing & tape				
	6.1.1	150mm sewer up to 1.50m deep	1,011	m		\$0.00
	6.1.2	150mm sewer 1.50m to 3.0m deep	554	m		\$0.00
	6.1.3	150mm sewer over 3.0m deep	165	m		\$0.00
	6.1.4	Provisional Item - Allowance for Excavation and Installation in Water Charged Ground		m		\$0.00
	6.2	Construct Manholes				
	6.2.1	Up to 1.5m Deep	18	each		\$0.00
	6.2.2	1.5m to 3m Deep	12	each		\$0.00
	6.2.3	Over 3m Deep	3	each		\$0.00
	6.3	Construct Lampholes				
	6.3.1	Construct Lampholes to 1.5m	10	each		\$0.00
	6.3.2	Construct Lampholes 1.5 to 3m	1	each		\$0.00
	6.4	House Junctions (including manhole inlets)		each		\$0.00
	6.4.1	100mm dia property sewer junction - Type B	27	each		\$0.00
	6.4.2	100mm dia property sewer junction - Type C1	27	each		\$0.00
	6.4.3	100mm dia property sewer junction - Type C2	11	each		\$0.00
	6.5	Bends				
	6.5.1	150mm 6° Bends	18	each		\$0.00
	6.5.2	150mm 11¼ ° Bends	5	each		\$0.00
	6.5.3	150mm 22½ ° Bends	3	each		\$0.00
	6.5.4	150mm 33¾° Bends	2	each		\$0.00
	6.5.5	150mm 45 ° Bends	1	each		\$0.00
	6.5.4	Connect to existing Manhole by Livingstone Shire	2	each		\$0.00
	6.6	Commissioning sewer main				
	6.6.1	Vaccum testing manholes	1	each		\$0.00
	6.6.2	Pressure testing of sewer	1	item		\$0.00
	6.6.3	CCTV inspection & reporting	1	item		\$0.00
7		WATER RETICULATION - POTABLE	\$0.00			
	7.1	Supply, excavate, bed, lay, joint and backfill pipes (incl tape)				
	7.1.1	DN63mm PE100 PN12.5 (Road 3)	80	m		\$0.00
	7.1.2	DN63mm PE100 PN12.5 (Road 5)	108	m		
	7.1.3	100mm Dia. PVC PN16	693	m		\$0.00
	7.2	Supply and Install Hydrants - Potable per CMDG-W060				
	7.2.1	Tee To Suit 100mm Dia.	10	each		\$0.00
	7.3	Remove temporary Ducksfoot Hydrants - Potable				
	7.3.1	Remopve and Dispose of 100mm Temporary Ducksfoot Hydrant to suit 100mm (road 5 near lot 66, Road 3 near lot 71, road 2 near lot 80, road 3 near lot 125, Road 4 near lot 106)	5	each		
	7.4	Supply and Install Stop Valves - Potable per CMDG-W060				
	7.3.1	To Suit 100mm Dia.	3	each		\$0.00
	7.4	Supply and Install Tees - Potable				
	7.4.1	100 x 100	1	each		\$0.00
	7.6	Supply and Install Bends including thrustblocks				
	7.6.1	100mm 6° Connector	43	each		\$0.00
	7.6.2	100mm 11¼° Bends	2	each		\$0.00
	7.6.3	100mm 22.5° Bends	1	each		\$0.00

		BILL OF QUANTITIES	DATE		1/07/2026 REV A	
		Item	Qty.	Unit	Rate	Total
	7.6.4	100mm 45° Bends	5	each		\$0.00
	7.6.5	100mm 90° Bends	1	each		\$0.00
	7.7	End Cap to suit 100mm Dia PVC Per CMDG-W-081				
	7.7.1	End cap and thrust block for cul de sac (Road 3 & road 5)	2	each		\$0.00
	7.8	Elongated tapping Band & 63mm Poly End Connector (Road 6) - per CMDG-W-081				
	7.8.1	Elongated tapping Band	4	each		\$0.00
	7.8.2	63mm Poly End Connector	4	each		\$0.00
	7.9	House Services - Main Cock & Tapping including Maincock cover per CMDG-W-090				
	7.9.1	Suit 63mm Potable main	4	each		\$0.00
	7.9.1	Suit 100mm Potable main	24	each		\$0.00
	7.10	Install Water Services including poly pipe and all fittings per CMDG-W-090				
	7.10.1	Water Service Under Road Including Conduit	13	each		\$0.00
	7.10.2	Water Service Short Side	11	each		\$0.00
	7.11	Disinfect Watermains - By Relevant Council - Provisional Item	1	each		\$0.00
	7.12	Connect to Existing Watermains - By Relevant Council - Prov. Item		each		\$0.00
	7.12.1	Pressure testing	1	each		\$0.00
8		ELECTRICAL AND COMMUNICATION	\$0.00			
	8.1	Supply and install electrical mains conduiting including bends, draw-wire, sand, bed, backfill, warning tape, all hard cover requirements, lot service connections				
	(a)	50mm (HD) for street lighting	144.45	m		\$0.00
	(b)	100mm LV	1637.1	m		\$0.00
	(c)	125mm HV	1829.7	m		\$0.00
	8.2	Electrical pillars, pad mount and switching stations (prov)				
	(a)	Supply & Install electrical pit (Type 3)	40	No		\$0.00
	8.3	Precast street light bases complete including supply of rag bolts and excluding 50mm dia orange class HD conduit connections to nearest turret				
	(a)	Minor street light base; unit length 1250mm	40	No		\$0.00
	8.4	Supply and install NBN telephone mains conduiting including bends, conduiting including bends, draw-wire, sand, bed, backfill and lot service connections				
	(a)	50mm	963	m		\$0.00
	8.5	Supply and Install NBN telephone pits complete in place to NBN specifications				
	(a)	Supply & install telecommunication pit (Type 2)	40	No		\$0.00
	6.6	Supply and Install Electrical Substation	1	No		\$0.00
9		EROSION AND SEDIMENT CONTROL - allowed for in BEW	\$0.00			
	9.1	Ongoing Maintenance of Erosion and Sediment Controls	1	item		\$0.00
	9.2	De-Commission redundant Sediment control and Re-instate to Finished Levels	1	item		\$0.00
10		LANDSCAPING & STREET FURNITURE	\$0.00			
	10.1	Signage - supply & intall - AUS-SPEC				
	10.1.1	Street Name Sign (per CMDG-R-080 & CMDG-R-081)	3	each		\$0.00
	10.2	Construct concrete pathway/shareway				
	10.2.1	1.5 wide	1,478	m		\$0.00
	10.3	Perambulator Ramps				
	10.3.1	1.5 wide pathway	8	m		\$0.00
	10.4	Mark and paint - As Per CMDG				
	10.4.1	Mark and paint all road crossings to kerb	1	item		\$0.00
	10.4.2	Mark all sewer as per CMDG-S-030	1	item		\$0.00
11		RETAINING WALLS- By Others	\$0.00			
12		NORTHERN BIO-RETENTION BASIN (near Lots 81 & 115)	\$0.00			
	12.1	Supply & construct bio-retention filter bed				
	12.1.1	Supply and lay 500mm thick filtration layer	390	m ²		\$0.00
	12.1.2	Supply and lay 100mm deep sand transition layer	390	m ²		\$0.00
	12.1.3	Supply and lay 200mm deep aggregate drainage layer	390	m ²		\$0.00
	12.2	Supply & install 100mm dia. unslotted pipe	6	m		\$0.00
	12.3	Supply & install 100mm dia. slotted pipe	54	m		\$0.00
	12.4	Supply & install subsoil drainage flushing points	4	each		\$0.00
	12.5	900X900 Low flow Stormwater pit with Raised Gate	1	each		\$0.00
	12.6	450mm Dia HDPE Stormwater Pipe	10	m		\$0.00
	12.7	Headwall to suit 450mm HDPE Pipe with outlet protection	1	m		\$0.00
	12.8	Supply & Construct Concrete Weir 10m x 1m together with Outlet Protection	1	each		\$0.00
13		WESTERN BIO-RETENTION BASIN (near Lot 93)	\$0.00			
	13.1	Supply & construct bio-retention filter bed				
	13.1.1	Supply and lay 500mm thick filtration layer	298	m ²		\$0.00
	13.1.2	Supply and lay 100mm deep sand transition layer	298	m ²		\$0.00
	13.1.3	Supply and lay 200mm deep aggregate drainage layer	298	m ²		\$0.00
	13.2	Supply & install 100mm dia. unslotted pipe	9	m		\$0.00
	13.3	Supply & install 100mm dia. slotted pipe	52	m		\$0.00
	13.4	Supply & install subsoil drainage flushing points	6	each		\$0.00
	13.5	900X900 Low flow Stormwater pit with Raised Gate	1	each		\$0.00
	13.6	450mm Dia HDPE Stormwater Pipe	10	m		\$0.00
	13.7	Headwall to suit 450mm HDPE Pipe with outlet protection	1	m		\$0.00
	13.8	Supply & Construct Concrete Weir 10m x 1m together with Outlet Protection	1	each		\$0.00

BILL OF QUANTITIES			DATE		1/07/2026 REV A	
		Item	Qty.	Unit	Rate	Total
14		TURF	\$0.00			
	14.1	Supply and Lay Turf to Drainage Swale near Lot 115 - Including Two Mows	596	m ²		
	14.2	Supply and Lay Turf behind New Kerb and Gutter - 1m Wide including Two Mows	2,346	m		
15		DE-ESTABLISHMENT	\$0.00			
	15.1	Final Site Presentation		Item		\$0.00
	15.1.1	Decommission site facilities		Item		\$0.00
	15.1.2	Final trim of footpaths, berms, batters following installation of water mains		Item		\$0.00
	15.1.3	Clean roads of all soil or other foreign materials (eg concrete, spills, general rubbish etc)		Item		\$0.00
	15.1.4	Preparation for and undertaking of final inspections & rectification of any defects		Item		\$0.00
16		MISCELLANEOUS ITEMS	\$0.00			
	18.1			Item		\$0.00
				Item		\$0.00
				Item		\$0.00
TOTAL (excl. GST)						\$0.00
GST			10%		\$0.00	
TOTAL (incl. GST)						\$0.00

TOTALS	Totals
1 ESTABLISHMENT	\$0.00
2 ROADWORKS	\$0.00
3 STORMWATER DRAINAGE	\$0.00
4 INTERLOT DRAINAGE	\$0.00
5 SUBSOIL DRAINAGE	\$0.00
6 SEWER RETICULATION	\$0.00
7 WATER RETICULATION - POTABLE	\$0.00
8 ELECTRICAL AND COMMUNICATION	\$0.00
9 EROSION AND SEDIMENT CONTROL - allowed for in BEW	\$0.00
10 LANDSCAPING & STREET FURNITURE	\$0.00
11 RETAINING WALLS- By Others	\$0.00
12 NORTHERN BIO-RETENTION BASIN (near Lots 81 & 115)	\$0.00
13 WESTERN BIO-RETENTION BASIN (near Lot 93)	\$0.00
14 TURF	\$0.00
15 DE-ESTABLISHMENT	\$0.00
16 MISCELLANEOUS ITEMS	\$0.00
Grand Total (exc GST)	\$0.00

* The estimates included herein are of a preliminary only for the purpose of quantity estimates, and undertaken to the best of our knowledge based on draft civil engineering designs done to date. It is the responsibility of the user of this provided documentation to satisfy themselves the suitability of the information for their purposes and utilisation.

* All costs and items are subject to final detailed civil design, council approval and formal tendering

* Costs exclude (but not limited to) the following;

 Council fees and charges, title searches, legal fees, authority fees and charges.

 Professional and management fees

 Certification

 Specialist consultancy, including, but not limited to; Geotechnical, structural, pressure sewer, electricity, telecommunications, bushfire, ecological or other specialist services.

 Any building &/or amenity construction

 Future planning consultancy, Development Applications and/or approval modifications etc.

 Additional works as a result of Force Majeure or other unforeseen circumstances.