

LIMESTONE CR ROAD YEPPOON						
Trunk Road Section C - OP WORKS						
BILL OF QUANTITIES			DATE		1/07/2026 REV A	
		Item	Qty.	Unit	Rate	Total
1	ESTABLISHMENT		\$0.00			
	1.1	Site establishment including fencing	1	Item		\$0.00
2	ROADWORKS		\$0.00			
	2.1	Trim and compact road subgrade	5,980	m ²		\$0.00
	2.2	Supply & Lay Gravel Pavement				
		Trunk Road CH325- 618.67				
		Sub-base 2 Material Type 2.5 min CBR 15 - 350mm Consolidated Depth (including 300mm behind Kerb)	1236.9	m ³		\$0.00
		Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	353.4	m ³		\$0.00
		Base Material Type 2.1 min CBR 80 - 110mm Consolidated Depth	331	m ³		\$0.00
		Roundabout				
		425mm consolidated depth DGS modified with Stabilment to produce UCS of 3 - 4 Mpa (incl 300mm behind Kerb and Gutter)	797	m ³		\$0.00
	2.3	Sealing				
	2.3.1	Primer seal - 10mm INCLUDING ROUNDABOUT	4,392	m ²		\$0.00
	2.3.2	Trunk Road CH282.2 - 624.3				
		40mm Asphaltic Concrete (DG14)	335	Tn		\$0.00
	2.3.3	Roundabout				
		40mm Asphaltic Concrete (AC10 + PMB)	133	Tn		\$0.00
		135mm total thick deep lift Asphaltic Concrete (DG14) in two layers to RAB	449	Tn		\$0.00
	2.4	Construct Kerb & Gutter as Per CMDG				
	2.4.1	Type 1 Barrier Kerb and Channel	588	m		\$0.00
	2.4.2	Type 4 Semi- Mountable Kerb toTraffic Island	155	m		\$0.00
	2.4.3	Type 5 Semi- Mountable Kerb to Roundabout	76	m		\$0.00
	2.5	Construct Roundabout Annulus	132	m ²		\$0.00
	2.6	150mm thick raised Concrete islands at roundabouts	123	m ²		\$0.00
	2.7	Plain Concrete Road Above Culvert to Engineers Design full width of road (back of Kerb to Back of Kerb)	823.4	m ²		\$0.00
	2.8	Testing -Arrange for tests & provide reports as per CMDG (Prov. Qty)				
	2.8.1	Subgrade Compaction	1	Item		\$0.00
	2.8.2	Gravel Compaction Base	1	Item		\$0.00
	2.8.3	Gravel Compaction Sub Base	1	Item		\$0.00
	2.8.4	Subgrade CBR	1	Item		\$0.00
	2.9	Construct Roundabout Annulus	132	m ²		\$0.00
	2.10	Concrete infill for islands	123	m ²		\$0.00
3	STORMWATER DRAINAGE		\$0.00			
	3.1	Supply, Excavate, Joint, Lay & Backfill incl compaction testing				
	3.1.1	375mm dia. HDPE	34.818	m		\$0.00
	3.1.2	675mm dia. RCP RRJ 'Class 3'	58.268	m		\$0.00
	3.1.3	750mm dia. RCP RRJ 'Class 3'	17.342	m		\$0.00
	3.1.4	3.6m x 0.9m RCBC	235.2	m		\$0.00
	3.1.5	3.6m x 1.2m RCBC	33.6	m		\$0.00
	3.2	Supply & Install Concrete Pits with Lintel				
	3.2.1	2.4m Lintel Type 'S' - STD CMDG Type A Gully Pit - SAG	2	each		\$0.00
	3.2.2	2.4m Lintel Type 'S' - STD CMDG Type A Gully Pit	1	each		\$0.00
	3.2.3	2.4m Lintel Type 'S' - Custom Pit (1200 x 900)	2	each		\$0.00
	3.2.4	2.4m Lintel Type 'S' - Custom Pit (1100x1100)	1	each		\$0.00
	3.3	Supply, Excavate, Install & Backfill Headwall to suit:				
	3.3.1	375mm DIA. HDPE (1/44)	1	each		
	3.3.2	750mm DIA. RCP (40-1)	1	each		
	3.4	Base Slab for Culverts per structural Engineers Details	1,072	m ²		\$0.00
	3.5	64 m Long Cast In-Situ Head Wall to Culverts (including Concrete Aprons) to Structural Engineers Details	2	Each		\$0.00
	3.6	Outlet Protection for Culvert System	1	each		\$0.00
	3.7	Outlet Protection for Headwalls	2	each		\$0.00
4	SUBSOIL DRAINAGE		\$0.00			
	4.1	Excavate, supply, bed, lay, joint and backfill pipe				
	4.1.1	100mm Dia. Draincoil: As per Specification incl. filter "sock"	588	m		\$0.00
	4.1.2	Subsoil drain flushing points (@ no greater than 50m Intervals)	12	each		\$0.00
5	WATER RETICULATION - POTABLE		\$0.00			
	5.1	Remove Temporary Ducksfoot Hydrant and Connect Main	2	Item		
	5.2	Supply, excavate, bed, lay, joint and backfill pipes (incl tape)				
	5.2.1	250mm Dia. PVC PN16	471	m		\$0.00
	5.3	Supply and Install Hydrants - Potable per CMDG-W060				
	5.3.1	To Suit 250mm Dia.	4	each		\$0.00
	5.3.2	Temporary Ducksfoot Hydrant to suit 250mm	1	each		\$0.00
	5.4	Supply and Install Stop Valves - Potable per CMDG-W060				
	5.4.1	To Suit 250mm Dia.	3	each		\$0.00
	5.4.2	Scour Valve to Suit 250mm Dia per CMDG-W-080	1	each		\$0.00
	5.5	Supply and Install Horizontal Bends including thrustblocks				
	5.5.1	250mm 6° Bends	1	each		\$0.00
	5.5.2	250mm 11¼° Bends	2	each		\$0.00
	5.5.3	250mm 22.5° Bends	2	each		\$0.00
	5.5.4	250mm 33 3/4° Bends (22.5° + 11.25°)	1	each		\$0.00
	5.5.5	250mm 45° Bends	6	each		\$0.00
	5.5.6	250mm 90° Bends	1	each		\$0.00

BILL OF QUANTITIES		DATE		1/07/2026 REV A	
	Item	Qty.	Unit	Rate	Total
	5.6 Supply and Install Tees - Potable				
	5.6.1 250 x 250	1	each		\$0.00
	5.7 Disinfect Watermains - By Relevant Council - Provisional Item	1	each		\$0.00
	5.8 Connect to Existing Watermains - By Relevant Council - Prov. Item				\$0.00
	5.8.1 Pressure testing	1	each		\$0.00
6	ELECTRICAL AND COMMUNICATION	\$0.00			
	6.1 Supply and install electrical mains conduiting including bends, draw-wire,				
	(a) 50mm (HD) for street lighting	45	m		\$0.00
	(b) 100mm LV	2007	m		\$0.00
	(c) 125mm HV	3116	m		\$0.00
	6.2 Electrical pillars, pad mount and switching stations (prov)				
	(a) Supply & Install electrical pit (Type 3)	16	No		\$0.00
	6.3 Precast street light bases complete including supply of rag bolts and				
	(a) Minor street light base; unit length 1250mm	10	No		\$0.00
	6.4 Supply and install NBN telephone mains conduiting including bends,				
	(a) 50mm	930	m		\$0.00
	6.5 Supply and Install NBN telephone pits complete in place to NBN				
	(a) Supply & install telecommunication pit (Type 2)	6	No		\$0.00
	6.6 Supply and Install Electrical Substation	1	No		\$0.00
7	EROSION AND SEDIMENT CONTROL				
	7.1 Ongoing Maintenance of Erosion and Sediment Controls	1	item		\$0.00
8	LANDSCAPING & STREET FURNITURE	\$0.00			
	8.1 Signage - Supply & Intall per CMDG-R-081				
	8.1.1 Street Name Sign (per CMDG-R-080 & CMDG-R-081)	1	each		\$0.00
	8.1.2 Roundabout Give Way	3	each		\$0.00
	8.1.3 Roundabout Ahead	3	each		\$0.00
	8.1.4 Keep Left Sign Installed on Roundabout Island	2	each		\$0.00
	8.1.5 Keep Left Sign Installed on Pedestrian Crossing Refuge	2	each		\$0.00
	8.1.6 Speed Signs (Prov Qty)	2	each		\$0.00
	8.1.7 Refuge Island Sign	2	each		\$0.00
	8.1.8 Bike Lane sign	2	each		\$0.00
	8.2 Construct concrete pathway/shareway				
	8.2.1 Supply and Lay Coloured concrete 3.2m Wide on Eastern Side of Road over Culvert	70	m		\$0.00
	8.2.2 Supply and Lay Coloured concrete 0.5m Wide on Eastern Side of Road over Culvert	70	m		\$0.00
	8.2.3 Supply and Lay Footpath 2.0 wide	695	m		\$0.00
	8.3 Supply and Install Plastic Lane Delineator kern for Bike Lane at Pedrestrian Refuge	28	m		\$0.00
	8.4 Supply and Install Handrails				
	8.4.1 1m High 2m wide to pedrestrian refuge island	2	Item		\$0.00
	8.4.2 1m High 2m wide to pedestrian refuge island at Roundabout	4	Item		\$0.00
	8.5 Perambulator Ramps to suit including tactile indicators to AUS-SPEC:				
	8.5.1 2.0 wide cycleway	6	each		\$0.00
	8.6 Supply and Install Powder Coated Bollards Bolted to concrete Over Culvert at 1m Centres	142	Each		\$0.00
	8.7 Supply and Install Powder Coated handrails Bolted to Culvert Head wall	140	m		\$0.00
	8.8 Mark and paint - AUS-SPEC				
	8.8.1 Mark and paint all road crossings to kerb	1	item		\$0.00
	8.8.2 All line marking noted below:				
	Double Continuous Centreline	364	m		\$0.00
	E4 Edge line	856	m		\$0.00
	Chevron Linemarking at Traffic Refuge	3	item		\$0.00
	Turf				
	8.9 Vehicle crossing - Heavy Duty to ASD204 (SPS Access)				
	8.9.1 Urban Commercial / Industrial Driveway	1	item		\$0.00
9	TURF	\$0.00			
	9.1 Supply and Lay Turf behind New Kerb and Gutter - 1m Wide including Two Mows	588	m		
	TOTAL (excl. GST)				\$0.00
	GST	10%			\$0.00
	TOTAL (Incl. GST)				\$0.00

BILL OF QUANTITIES		DATE		1/07/2026 REV A	
	Item	Qty.	Unit	Rate	Total

TOTALS	Totals
1 ESTABLISHMENT	\$0.00
2 ROADWORKS	\$0.00
3 STORMWATER DRAINAGE	\$0.00
4 SUBSOIL DRAINAGE	\$0.00
5 WATER RETICULATION - POTABLE	\$0.00
6 ELECTRICAL & COMMUNICATION	\$0.00
7 EROSION AND SEDIMENT CONTROL	\$0.00
8 LANDSCAPING & STREET FURNITURE	\$0.00
9 TURF	\$0.00
Grand Total (exc GST)	\$0.00

* The estimates included herein are of a preliminary only for the purpose of quantity estimates, and undertaken to the best of our knowledge based on draft civil engineering designs done to date. It is the responsibility of the user of this provided documentation to satisfy themselves the suitability of the information for their purposes and utilisation.

* All costs and items are subject to final detailed civil design, council approval and formal tendering

* Costs exclude (but not limited to) the following;

- Council fees and charges, title searches, legal fees, authority fees and charges.
- Professional and management fees
- Certification
- Specialist consultancy, including, but not limited to; Geotechnical, structural, pressure sewer, electricity, telecommunications, bushfire, ecological or other specialist services.
- Any building &/or amenity construction
- Future planning consultancy, Development Applications and/or approval modifications etc.
- Additional works as a result of Force Majeure or other unforeseen circumstances.