

REQUEST FOR QUOTE (RFQ) – SEWER RETICULATION PACKAGE

Project: Limestone Creek Estate Development – Yeppoon

Project No.: 5614

Principal Contractor: McIntosh Civil

Date: 07-15-2026

Attention: To Whom It May Concern

McIntosh Civil invites quotations from suitably qualified civil subcontractors for the **Sewer Reticulation Package** associated with the **Limestone Creek Estate Development, Yeppoon QLD**.

The works are to be completed in accordance with the Land Dynamics Australia engineering drawings, Livingstone Shire Council requirements, Capricorn Municipal Development Guidelines (CMDG), applicable Australian Standards and all relevant sewer infrastructure specifications.

SCOPE OF WORKS — SEWER RETICULATION

Provide all labour, plant, materials, equipment, supervision and incidentals necessary to complete the sewer reticulation works in accordance with the supplied drawings and specifications.

Scope Includes

Stages 1 & 2

Supply, excavate, bed, lay, joint and backfill sewer mains including compaction testing, marker tape and all associated works:

- 667m of 150mm sewer main up to 1.5m deep.
- 1,410m of 150mm sewer main between 1.5m and 3.0m deep.
- 27m of 150mm sewer main greater than 3.0m deep.
- 591m of 300mm sewer main between 1.5m and 3.0m deep.
- 30m of 300mm sewer main greater than 3.0m deep.

Construction of:

- 13 sewer manholes up to 1.5m deep.
- 34 sewer manholes between 1.5m and 3.0m deep.
- 4 sewer manholes greater than 3.0m deep.

Construction of:

- 7 lampholes up to 1.5m deep.
- 3 lampholes between 1.5m and 3.0m deep.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

Property connections including:

- **26 Type B sewer junctions.**
- **21 Type C1 sewer junctions.**
- **27 Type C2 sewer junctions.**
- **12 Type D sewer junctions.**

Associated fittings including bends and connections to existing infrastructure.

Stages 3, 4, 5 & 6

Supply, excavate, bed, lay, joint and backfill sewer mains including compaction testing, marker tape and all associated works:

- **1,011m of 150mm sewer main up to 1.5m deep.**
- **554m of 150mm sewer main between 1.5m and 3.0m deep.**
- **165m of 150mm sewer main greater than 3.0m deep.**

Construction of:

- **18 sewer manholes up to 1.5m deep.**
- **12 sewer manholes between 1.5m and 3.0m deep.**
- **3 sewer manholes greater than 3.0m deep.**

Construction of:

- **10 lampholes up to 1.5m deep.**
- **1 lamphole between 1.5m and 3.0m deep.**

Property connections including:

- **27 Type B sewer junctions.**
- **27 Type C1 sewer junctions.**
- **11 Type C2 sewer junctions.**

Associated fittings including bends and connections to existing infrastructure.

Testing & Commissioning

The package shall include:

- Vacuum testing of all manholes.
- Pressure testing of sewer mains.
- CCTV inspection and reporting.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

- Defect rectification arising from CCTV inspections.
- Submission of all commissioning records and compliance documentation.
- Practical completion certification.

DRAWING REFERENCES

Please base your quotation on the following documentation:

General

- **5614-1000** – Cover Sheet & Drawing Index.
- **5614-1001** – Overall Layout Plan.

Civil Layouts

- **5614-1002 to 1005** – General Layout Plans.

Sewer Infrastructure

- Sewer reticulation layout drawings.
- Longitudinal sections.
- Manhole schedules.
- Sewer connection details.
- Standard sewer construction details.
- Relevant civil design documentation contained within the tender package.

BOQ

- **Sewer Subcontractors.xlsx**
 - Stages 1 & 2 Sewer Reticulation.
 - Stages 3, 4, 5 & 6 Sewer Reticulation.

Additional documentation can be provided upon request.

INCLUSIONS

Your quotation shall include, as a minimum:

- Mobilisation and demobilisation.
- Excavation and trench support.
- Supply and installation of all sewer mains.
- Bedding, embedment and backfilling.
- Compaction testing.
- Marker tape and tracer requirements.
- Manhole construction.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

- Lamphole construction.
- Sewer junction construction.
- All fittings, bends and connections.
- Dewatering where required.
- Connection to existing infrastructure.
- Testing and commissioning.
- CCTV inspections and reporting.
- Quality assurance documentation.
- Cleanup and disposal of surplus materials.
- Protection of completed works until handover.

EXCLUSIONS

Unless specifically included within your offer, the following shall be excluded:

- Bulk earthworks outside sewer trench excavation.
- Stormwater drainage.
- Water reticulation.
- Kerb and channel works.
- Pavement construction and reinstatement outside trench extents.
- Asphalt surfacing.
- Traffic control (by McIntosh Civil unless otherwise directed).
- Survey control establishment.
- Utility authority works.

SUBMISSION REQUIREMENTS

Please provide:

- Lump Sum Price for the complete package.
- Schedule of rates including:
 - 150mm sewer main by depth category (\$/m).
 - 300mm sewer main by depth category (\$/m).
 - Manholes by depth category (\$/No.).
 - Lampholes (\$/No.).
 - Property junctions by type (\$/No.).
 - Sewer bends and fittings (\$/No.).
 - Water charged ground excavation (\$/m).
- Programme duration.
- Earliest commencement date.
- Proposed methodology.
- Assumptions and exclusions.
- Validity period of quotation.





SUBMISSION INSTRUCTIONS

Send quotations to:

Ben McIntosh

 ben@mcintoshcivil.au

 0411 894 191

Chris Abad – Estimating Support

 chris@mcintoshcivil.au

Email Subject:

RFQ – Sewer Reticulation Package – Limestone Creek Estate Yeppoon

We appreciate your interest and look forward to receiving your quotation.

Kind Regards,

McIntosh Civil

Tendering & Procurement Team



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670