

LIMESTONE CR ROAD YEPPOON					
STAGE 1 & 2 - OP WORKS					
BILL OF QUANTITIES			DATE	1/07/2026 Rev A	
	Item	Qty.	Unit	Rate	Total
1	ESTABLISHMENT	\$0.00			
1.1	Site establishment including fencing	1			\$0.00
2	ROADWORKS	\$0.00			
2.1	Trim and compact road subgrade	17,152	m ²		\$0.00
2.2	Supply & Lay Gravel Pavement				
	Road 1 CH44.1 -CH421.5 including KRA, B, C & D				
	Sub-base 2 Material Type 2.5 min CBR 15 - 200mm Consolidated Depth (including 300mm behind Kerb)	903.18	m ³		\$0.00
	Sub-base 1 Material Type 2.3 min CBR 45 - 180mm Consolidated Depth (including 300mm behind Kerb)	812.862	m ³		\$0.00
	Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	382.3	m ³		\$0.00
	Road 1 CH4474.78 -CH743.36				
	Sub-base 2 Material Type 2.5 min CBR 15 - 200mm Consolidated Depth (including 300mm behind Kerb)	609.36	m ³		\$0.00
	Sub-base 1 Material Type 2.3 min CBR 45 - 180mm Consolidated Depth (including 300mm behind Kerb)	548.424	m ³		\$0.00
	Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	258.11	m ³		\$0.00
	Road 2 CH28.57- CH670				
	Sub-base 2 Material Type 2.5 min CBR 15 - 185mm Consolidated Depth (including 300mm behind Kerb)	1031.412	m ³		\$0.00
	Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	557.52	m ³		\$0.00
	Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	442.02	m ³		\$0.00
	Road 5 CH 4.84 - CH41.13				
	Sub-base 1 Material Type 2.3 min CBR 45 - 180mm Consolidated Depth (including 300mm behind Kerb)	63.414	m ³		\$0.00
	Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	29.45	m ³		\$0.00
	Road 6 CH -60.53 To END				
	Sub-base 2 Material Type 2.5 min CBR 15 - 170mm Consolidated Depth (including 300mm behind Kerb)	294.542	m ³		\$0.00
	Sub-base 1 Material Type 2.5 min CBR 15 - 100mm Consolidated Depth (including 300mm behind Kerb)	173.26	m ³		\$0.00
	Base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth	142.51	m ³		\$0.00
	Road 7 CH 3.5 To 73				
	Sub-base 2 Material Type 2.5 min CBR 15 - 170mm Consolidated Depth (including 300mm behind Kerb)	97.189	m ³		\$0.00
	Sub-base 1 Material Type 2.3 min CBR 45 - 100mm Consolidated Depth (including 300mm behind Kerb)	57.17	m ³		\$0.00
	Base Material Type 2.1 min CBR 80 - 100mm Consolidated Depth	46.1	m ³		\$0.00
	Roundabout - ROAD 1				
	345mm consolidated depth DGS modified with Stabilment to produce UCS of 3 - 4 Mpa (incl 300mm behind Kerb and Gutter)	468.34	m ³		\$0.00
2.3	Sealing				
	Primer seal - 10mm INCLUDING ROUNDABOUT	14,366	m ²		\$0.00
	Road 1 CH44.1 -CH421.5 including KRA, B, C & D				
	40mm Asphaltic Concrete (DG14)	367	Tn		\$0.00
	Road 1 CH474.78 -CH743.36				
	40mm Asphaltic Concrete (DG14)	248	Tn		\$0.00
	Road 2 CH28.57- CH670				
	25mm Asphaltic Concrete (DG10)	265	Tn		\$0.00
	Road 5 CH 4.84 - CH41.13				
	25mm Asphaltic Concrete (DG10)	18	Tn		\$0.00
	Road 6 CH -60.53 To END				
	25mm Asphaltic Concrete (DG10)	86	Tn		\$0.00
	Road 7 CH 3.5 To 73				
	25mm Asphaltic Concrete (DG10)	28	Tn		\$0.00
	Roundabout - ROAD 1				
	40mm Asphaltic Concrete (AC10 + PMB)	117	Tn		\$0.00
	135mm total thick deep lift Asphaltic Concrete (DG14) in two layers to RAB	395	Tn		\$0.00
2.4	Construct Kerb & Gutter				
2.4.1	Type 2 Mountable Kerb and Channel	3,253	m		\$0.00
2.4.2	Type 4 Semi- Mountable Kerb to Roundabout Island	104	m		\$0.00
2.4.3	Type 5 Semi- Mountable Kerb to Roundabout	51	m		\$0.00
2.5	Construct Roundabout Annulus	81.6	m ²		\$0.00
2.6	150mm thick raised Concrete islands at roundabouts	78	m ²		\$0.00
2.7	Supply & lay compacted sand or similar sub-base course to Driveways (subject to Geotech Testing)				
2.7.1	Driveway Lot 6 - 150mm consolidated depth	20	m ³		\$0.00
2.7.2	Driveway Lot 28 - 150mm consolidated depth	22	m ³		\$0.00
2.8	Supply & lay Concrete Driveway (including Layback) CMDG-R-041				
2.8.1	Driveway Lot 6 - 125mm Reinforced Concrete Driveway	133	m ²		\$0.00
2.8.2	Driveway Lot 28 - 125mm Reinforced Concrete Driveway	149	m ²		\$0.00
2.9	Testing -Arrange for tests & provide reports as per CMDG (Prov. Qty)				
2.9.1	Subgrade Compaction	1	Item		\$0.00
2.9.2	Gravel Compaction Base	1	Item		\$0.00
2.9.3	Gravel Compaction Sub Base	1	Item		\$0.00
2.9.4	Subgrade CBR	1	Item		\$0.00

BILL OF QUANTITIES			DATE		1/07/2026 Rev A	
	Item		Qty.	Unit	Rate	Total
	2.10	Construct Temporaty Turning Circle Road 2, Road 5 & Road 7	3	each		\$0.00
3	STORMWATER DRAINAGE		\$0.00			
	3.1	Supply, Excavate, Joint, Lay & Backfill incl compaction testing				
	3.1.1	375mm dia. HDPE	584.5	m		\$0.00
	3.1.2	450mm dia. HDPE	163.5	m		\$0.00
	3.1.3	525mm dia. HDPE	311.4	m		\$0.00
	3.1.4	600mm dia. HDPE	309.0	m		\$0.00
	3.1.5	675mm dia. RCP RRJ 'Class 3'	34.4	m		\$0.00
	3.1.6	750mm dia. RCP RRJ 'Class 3'	19.9	m		\$0.00
	3.1.7	825mm dia. RCP RRJ 'Class 3'	37.6	m		\$0.00
	3.1.8	900mm dia. RCP RRJ 'Class 3'	117.9	m		\$0.00
	3.2	Construct Concrete Pits				
	3.2.1	2.4m Lintel Type 'S' - STD CMDG Type A Gully Pit - SAG	7	each		\$0.00
	3.2.2	2.4m Lintel Type 'S' - STD CMDG Type A Gully Pit	53	each		\$0.00
	3.3	Supply & Construct Custom Concrete Pits				
	3.3.1	Custom grated Junction Pit To plan Detail including Structural Design - Pit 5/1 (1100x900)	1	Item		\$0.00
	3.3.2	Custom grated Junction Pit To plan Detail including Structural Design - Pit 2/18 (2100x900)	1	Item		\$0.00
	3.3.3	Custom grated Junction Pit To plan Detail including Structural Design - Pit 3/18 (2100x1300)	1	Item		\$0.00
	3.3.4	Custom grated Junction Pit To plan Detail including Structural Design - Pit 4/18 (1300x1200)	1	Item		\$0.00
	3.3.5	Custom grated Junction Pit To plan Detail including Structural Design - Pit 2/20 (1200x900)	1	Item		\$0.00
	3.3.6	Custom grated Junction Pit To plan Detail including Structural Design - Pit 5/18 (1100x1200)	1	Item		\$0.00
	3.3.7	Custom grated Junction Pit To plan Detail including Structural Design - Pit 6/18 (1100x900)	1	Item		\$0.00
	3.4	Supply, Excavate, Install & Backfill Headwall to suit:				
	3.4.1	Twin 900mm DIA. RCP (1/18)	1	each		\$0.00
	3.4.2	Temporary headwall to suit 600mm DIA. HDPE (5/1) including tail out Swale	1	each		\$0.00
	3.4.3	Temporary headwall to suit 375mm DIA. HDPE (10/9) including tail out Swale	1	each		\$0.00
	3.5	Outlet Protection to headwall	1	each		\$0.00
4	INTERLOT DRAINAGE		\$0.00			
	4.1	Supply, excavate, bed, lay, joint and backfill pipe				
	4.1.1	150mm Dia. uPVC.	126.3	m		\$0.00
	4.1.2	200mm Dia. uPVC.	122.9	m		\$0.00
	4.1.3	225mm Dia. uPVC.	134.2	m		\$0.00
	4.1.4	300mm Dia. uPVC.	250.4	m		\$0.00
	4.2	Supply and Install Stormwater Junctions				
	4.2.1	Junctions to IAD pits	26	each		\$0.00
	4.2.2	Supply and Install Kerb Adaptor in accordance with CMDG -R-061	44	each		\$0.00
	4.2.3	Supply and Install 100mm DIA uPVC junction to lot from Kerb Adaptor in Accordance with CMDG-R-061	264	m		\$0.00
	4.3	Supply and Install Pre-Cast IAD Pits				
	4.3.1	Std. Inspection Pit 600 x 600 mm	6	each		\$0.00
	4.3.2	Std. Inspection Pit 600 x 900 mm	7	each		\$0.00
	4.3.3	Std. Inspection Pit 900 x 900 mm	13	each		\$0.00
	4.4	Supply, Excavate, Install & Backfill Headwall to suit:				
	4.4.1	225mm DIA. HDPE (32-1)	1	Each		\$0.00
	4.5	Concrete Outlet Protection				
	4.5.1	Outlet scour protection	1	item		\$0.00
5	SUBSOIL DRAINAGE		\$0.00			
	5.1	Excavate, supply, bed, lay, joint and backfill pipe				
	5.1.1	100mm Dia. Draincoil: As per Specification incl. filter "sock"	3,253	m		\$0.00
	5.1.2	Subsoil drain flushing points (@ no greater than 50m Intervals)	65	each		\$0.00
6	SEWER RETICULATION		\$0.00			
	6.1	Supply, Excavate, bed, lay, joint & backfill incl compaction testing & tape				
	6.1.1	150mm sewer up to 1.50m deep	667	m		\$0.00
	6.1.2	150mm sewer 1.50m to 3.0m deep	1,410	m		\$0.00
	6.1.3	150mm sewer over 3.0m deep	27	m		\$0.00
	6.1.4	300mm sewer 1.50m to 3.0m deep	591	m		\$0.00
	6.1.5	300mm sewer over 3.0m deep	30	m		\$0.00
	6.1.6	Provisional Item - Allowance for Excavation and Installation in Water Charged Ground		m		\$0.00
	6.2	Construct Manholes				
	6.2.1	Up to 1.5m Deep	13	each		\$0.00
	6.2.2	1.5m to 3m Deep	34	each		\$0.00
	6.2.3	Over 3m Deep	4	each		\$0.00
	6.3	Construct Lampholes				
	6.3.1	Construct Lampholes to 1.5m	7	each		\$0.00
	6.3.2	Construct Lampholes 1.5 to 3m	3	each		\$0.00
	6.4	House Junctions - into line		each		\$0.00
	6.4.1	100mm dia property sewer junction - Type B	26	each		\$0.00
	6.4.2	100mm dia property sewer junction - Type C1	21	each		\$0.00
	6.4.3	100mm dia property sewer junction - Type C2	27	each		\$0.00
	6.4.4	100mm dia property sewer junction - Type D	12	each		\$0.00

BILL OF QUANTITIES			DATE	1/07/2026 Rev A		
		Item	Qty.	Unit	Rate	Total
	6.5	Bends				
	6.5.1	150mm 6° Bends	12	each		\$0.00
	6.5.2	150mm 11¼ ° Bends	2	each		\$0.00
	6.5.3	150mm 22½ ° Bends	1	each		\$0.00
	6.5.4	150mm 45 ° Bends	2	each		\$0.00
	6.5.5	Connect to existing Manhole by Livingstone Shire	2	each		\$0.00
	6.6	Commissioning sewer main				
	6.6.1	Vaccum testing manholes	1	item		\$0.00
	6.6.2	Pressure testing of sewer	1	item		\$0.00
	6.6.3	CCTV inspection & reporting	1	item		\$0.00
7		WATER RETICULATION TO WESTERN SIDE OF ROUNDABOUT ON ROAD 1 - POTABLE	\$0.00			
	7.1	Supply, excavate, bed, lay, joint and backfill pipes (incl tape)				
	7.1.1	DN63mm PE100 PN12.5 (Road 6)	83	m		\$0.00
	7.1.2	100mm Dia. PVC PN16	630	m		\$0.00
	7.1.3	200mm Dia. PVC PN16	322	m		\$0.00
	7.1.4	250mm Dia. PVC PN16 FROM EAST LOT 1706 TO WESTERN SIDE OF ROAD 1	976	m		\$0.00
	7.2	Supply and Install Hydrants - Potable per CMDG-W060				
	7.2.1	Tee To Suit 100mm Dia.	9	each		\$0.00
	7.2.2	Tee To Suit 200mm Dia.	3	each		\$0.00
	7.2.3	Tee To Suit 250mm Dia.	13	each		\$0.00
	7.2.4	Temporary Ducksfoot Hydrant to suit 100mm (road 5 near lot 66, Road 3 near lot 71, road 2 near lot 80, road 3 near lot 125, Road 4 near lot 106)	5	each		\$0.00
	7.2.5	Temporary Ducksfoot Hydrant to suit 200mm (near lot 81)	1	each		\$0.00
	7.3	Supply and Install Stop Valves - Potable per CMDG-W060				
	7.3.1	To Suit 100mm Dia.	10	each		\$0.00
	7.3.2	To Suit 200mm Dia.	5	each		\$0.00
	7.3.3	To Suit 250mm Dia.	6	each		\$0.00
	7.3.4	Scour Valve to Suit 100mm Dia (including connection to Kerb Side Drainage Pit) per CMDG-W-080	1	Item		\$0.00
	7.4	Supply and Install Tees - Potable				
	7.4.1	100 x 200	1	each		\$0.00
	7.4.2	100 x 250	2	each		\$0.00
	7.4.3	200 x 200	1	each		\$0.00
	7.4.4	250 x 250	4	each		\$0.00
	7.5	Supply and Install Reducers - Potable				
	7.5.1	100 x 200	1	each		\$0.00
	7.5.2	100 x 250	3	each		\$0.00
	7.5.3	100 x 200	1	each		\$0.00
	7.5.4	200 x 250	1	each		\$0.00
	7.6	Supply and Install Bends including thrustblocks				
	7.6.1	100mm 6° Connector	24	each		\$0.00
	7.6.2	100mm 11¼° Bends	3	each		\$0.00
	7.6.3	100mm 45° Bends	7	each		\$0.00
	7.6.4	200mm 6° Connector	7	each		\$0.00
	7.6.5	200mm 11¼° Bends	5	each		\$0.00
	7.6.6	200mm 11¼° Bends (vertical)	2	Each		\$0.00
	7.6.7	200mm 45° Bends	4	each		\$0.00
	7.6.8	200mm 90° Bends	1	each		\$0.00
	7.6.9	250mm 6° Connector	29	each		\$0.00
	7.6.10	250mm 11¼° Bends	5	each		\$0.00
	7.6.11	250mm 22.5° Bends	3	each		\$0.00
	7.6.12	250mm 33 3/4° Bends (22.5° + 11.25°)	3	each		\$0.00
	7.6.13	250mm 45° Bends	7	each		\$0.00
	7.6.14	250mm 90° Bends	2	each		\$0.00
	7.7	End Cap to suit 100mm Dia PVC Per CMDG-W-081				
	7.7.1	End cap and thrust block for cul de sac (Road 6)	1	each		\$0.00
	7.8	Elongated tapping Band & 63mm Poly End Connector (Road 6) - per CMDG-				
	7.8.1	Elongated tapping Band	2	each		\$0.00
	7.8.2	63mm Poly End Connector	2	each		\$0.00
	7.9	House Services - Main Cock & Tapping including Maincock cover per CMDG-W-090				
	7.9.1	Suit 63mm Potable main	3	each		\$0.00
	7.9.2	Suit 100mm Potable main	24	each		\$0.00
	7.9.3	Suit 200mm Potable main	10	each		\$0.00
	7.9.4	Suit 250mm Potable main	19	each		\$0.00
	7.10	Install Water Services including poly pipe and all fittings per CMDG-W-090				
	7.10.1	Water Service Under Road Including Conduit	24	each		\$0.00
	7.10.2	Water Service Short Side	30	each		\$0.00
	7.11	Disinfect Watermains - By Relevant Council - Provisional Item	1	each		\$0.00
	7.12	Connect to Existing Watermains - By Relevant Council - Prov. Item		each		\$0.00
	7.12.1	Pressure testing	1	each		\$0.00
8		WATER RETICULATION FROM WESTERN SIDE ROUNDABOUT ROAD 1 TO MAIN COLLECTOR ROAD - POTABLE	\$0.00			
	8.1	Supply, excavate, bed, lay, joint and backfill pipes (incl tape)				
	8.1.1	100mm Dia. PVC PN16	38	m		\$0.00
	8.1.2	250mm Dia. PVC PN16	400	m		\$0.00
	8.2	Supply and Install Hydrants - Potable				
	8.2.1	Tee To Suit 250mm Dia.	6	each		\$0.00
	8.2.2	Temporary Ducksfoot Hydrant to Suit 100mm Dia	2	each		
	8.3	Supply and Install Stop Valves - Potable				
	8.3.1	To Suit 100mm Dia.	2	each		\$0.00

BILL OF QUANTITIES		DATE		1/07/2026 Rev A	
	Item	Qty.	Unit	Rate	Total
	8.3.2 To Suit 250mm Dia.	2	each		\$0.00
	8.4 Supply and Install Tees - Potable				
	8.4.1 250 x 100	2			
	8.5 Supply and Install Bends including thrustblocks				
	8.5.1 100mm 22.5° Bend	1	each		\$0.00
	8.5.2 100mm 45° Bend	2	each		\$0.00
	8.5.3 250mm 6° Connector	11	each		\$0.00
	8.6 House Services - Main Cock & Tapping including Maincock cover				
	8.6.1 Suit 250mm Potable main	13	each		\$0.00
	8.7 Install Water Services including poly pipe and all fittings per CMDG-W-090				
	8.7.1 Water Service Under Road Including Conduit	3	each		\$0.00
	8.7.2 Water Service Short Side	10	each		\$0.00
	8.8 Disinfect Watermains - By Relevant Council - Provisional Item	1	each		\$0.00
9	LEAD IN WATER RETICULATION (CONNECTION TO WATERMAIN IN ADELAIDE PARK RD) - PROVISION ITEM ONLY	\$0.00			
	9.1 Supply, excavate, bed, lay, joint and backfill pipes (incl tape)				
	9.1.1 250mm Dia. PVC PN16	402	m		\$0.00
	9.2 Supply and Install Hydrants - Potable				
	9.2.1 To Suit 250mm Dia.	7	each		\$0.00
	9.2.2 To suit 250 Dia	7	each		\$0.00
	9.3 Supply and Install Stop Valves - Potable				
	9.3.1 To Suit 250mm Dia.	1	each		\$0.00
	9.4 Bends including thrustblocks				
	9.4.1 250mm 6° Bends	8	each		\$0.00
	9.4.2 250mm 11¼° Bends	4	each		\$0.00
	9.4.3 250mm 22½° Bends	4	each		\$0.00
	9.4.4 250mm 33 3/4° Bends	2	each		\$0.00
	9.4.5 250mm 45° Bends	1	each		\$0.00
	9.5 Connect to Existing Watermains - By Relevant Council - Prov. Item				
	9.5.1 Pressure testing	1	each		\$0.00
	9.5.2 Connect to existing mains by Livingstone Shire Council	1	each		\$0.00
10	ELECTRICAL AND COMMUNICATION	\$0.00			
	10.1 Supply and install electrical mains conduiting including bends, draw-wire, sand, bed, backfill, warning tape, all hard cover requirements, lot service connections				
	10.1.1 50mm (HD) for street lighting (prov QTY ONLY)	244.5	m		\$0.00
	10.1.2 100mm LV (prov QTY ONLY)	2771	m		\$0.00
	10.1.3 125mm HV (prov QTY ONLY)	3097	m		\$0.00
	10.2 Electrical pillars, pad mount and switching stations (prov)				
	10.2.1 Supply & Install electrical pit (Type 3) (prov QTY ONLY)	40	No		\$0.00
	10.3 Precast street light bases complete including supply of rag bolts and excluding 50mm dia orange class HD conduit connections to nearest turret				
	10.3.1 Minor street light base; unit length 1250mm (prov QTY ONLY)	27	No		\$0.00
	10.4 Supply and install NBN telephone mains conduiting including bends, conduiting including bends, draw-wire, sand, bed, backfill and lot service connections				
	10.4.1 50mm (prov QTY ONLY)	1630	m		\$0.00
	10.5 Supply and Install NBN telephone pits complete in place to NBN specifications				
	10.5.1 Supply & install telecommunication pit (Type 2) (prov QTY ONLY)	40	No		\$0.00
	10.6 Supply and Install Electrical Substation	1	No		\$0.00
11	EROSION AND SEDIMENT CONTROL - allowed for in BEW	\$0.00			
	11.1 Ongoing Maintenance of Erosion and Sediment Controls	1	item		\$0.00
	11.2 De-commission redundant Sediment control and Re-instate to Finished Levels	1	item		\$0.00
12	LANDSCAPING & STREET FURNITURE	\$0.00			
	12.1 Signage - supply & intall - AUS-SPEC				
	12.1.1 Street Name Sign (per CMDG-R-080 & CMDG-R-081)	6	each		\$0.00
	12.1.2 Roundabout Give Way	4	each		\$0.00
	12.1.3 Roundabout Ahead Sign	4	each		\$0.00
	12.1.4 Keep Left Sign Installed on Roundabout Island	4	each		\$0.00
	12.1.6 Pedrestrian Crossing Sign (both sides of road)	4	each		\$0.00
	12.2 Construct concrete pathway/shareway				
	12.2.1 1.5 wide	1,094	m		\$0.00
	12.2.2 2.0 wide	1,379	m		\$0.00
	12.3 Install Perambulator Ramps Per CMDG-R-050				
	12.3.1 To suit 1.5 wide pathway	6	each		\$0.00
	12.3.2 To Suit 2.0 wide cycleway	12	each		\$0.00
	12.4 Mark and paint - As Per CMDG				
	12.4.1 Mark and paint all road crossings to kerb	1	item		\$0.00
	12.4.2 Mark all sewer as per CMDG-S-030	1	item		\$0.00
	12.4.3 All line marking noted below:				
	E4 Edge line to Roundabout Island	104	m		\$0.00
	Give Way line to Roundabout	25	m		\$0.00
	Pedrestrian Crossing	2	item		\$0.00
	12.5 Supply and Install Handrails				
	12.5.1 1m High 2m wide to pedestrian refuge island at Roundabout	2	Item		\$0.00

BILL OF QUANTITIES			DATE	1/07/2026 Rev A		
		Item	Qty.	Unit	Rate	Total
13		SOUTH BIO-RETENTION BASIN (BEHIND LOT 20)	\$0.00			
	13.1	Supply & construct bio-retention filter bed				
	13.1.1	Supply and lay 500mm thick filtration layer	436	m ²		\$0.00
	13.1.2	Supply and lay 100mm deep sand transition layer	436	m ²		\$0.00
	13.1.3	Supply and lay 200mm deep aggregate drainage layer	436	m ²		\$0.00
	13.2	Supply & install 100mm dia. unslotted pipe	15	m		\$0.00
	13.3	Supply & install 100mm dia. slotted pipe	118	m		\$0.00
	13.4	Supply & install subsoil drainage flushing points	8	each		\$0.00
	13.5	900X900 Low flow Stormwater pit with Raised Grate	1	each		\$0.00
	13.6	450mm Dia HDPE Stormwater Pipe	17	m		\$0.00
	13.7	Headwall to suit 450mm HDPE Pipe with outlet protection	1	Each		\$0.00
	13.8	Supply & Construct Concrete Weir 7.2m x 1m together with Outlet Protection	1	item		\$0.00
14		DE-ESTABLISHMENT	\$0.00			
	14.1	Final Site Presentation		Item		\$0.00
	14.1.1	Decommission site facilities	1	Item		\$0.00
	14.1.2	Final trim of footpaths, berms, batters following installation of water mains	1	Item		\$0.00
	14.1.3	Clean roads of all soil or other foreign materials (eg concrete, spills, general rubbish etc)	1	Item		\$0.00
	14.1.4	Preparation for and undertaking of final inspections & rectification of any defects	1	Item		\$0.00
15		TURF	\$0.00			
	15.1	Supply and Lay Turf behind New Kerb and Gutter - 1m Wide including Two Mows	3,253	m		
16		MISCELLANEOUS ITEMS	\$0.00			
				Item		\$0.00
				Item		\$0.00
				Item		\$0.00
				Item		\$0.00
TOTAL (excl. GST)						\$0.00
GST			10%			\$0.00
TOTAL (incl. GST)						\$0.00

TOTALS	Totals
1 ESTABLISHMENT	\$0.00
2 ROADWORKS	\$0.00
3 STORMWATER DRAINAGE	\$0.00
4 INTERLOT DRAINAGE	\$0.00
5 SUBSOIL DRAINAGE	\$0.00
6 SEWER RETICULATION	\$0.00
7 WATER RETICULATION TO WESTERN SIDE OF ROUNDABOUT ON ROAD 1 - POTABLE	\$0.00
8 WATER RETICULATION FROM WESTERN SIDE ROUNDABOUT ROAD 1 TO MAIN COLLECTOR ROAD - POTABLE	\$0.00
9 LEAD IN WATER RETICULATION (CONNECTION TO WATERMAIN IN ADELAIDE PARK RD) - PROVISION ITEM ONLY	\$0.00
10 ELECTRICAL AND COMMUNICATION	\$0.00
11 EROSION AND SEDIMENT CONTROL - allowed for in BEW	\$0.00
12 LANDSCAPING & STREET FURNITURE	\$0.00
13 SOUTH BIO-RETENTION BASIN (BEHIND LOT 20)	\$0.00
14 DE-ESTABLISHMENT	\$0.00
15 TURF	\$0.00
16 MISCELLANEOUS ITEMS	\$0.00
Grand Total (exc GST)	\$0.00

* The estimates included herein are of a preliminary only for the purpose of quantity estimates, and undertaken to the best of our knowledge based on draft civil engineering designs done to date. It is the responsibility of the user of this provided documentation to satisfy themselves the suitability of the information for their purposes and utilisation.

* All costs and items are subject to final detailed civil design, council approval and formal tendering

* Costs exclude (but not limited to) the following;

Council fees and charges, title searches, legal fees, authority fees and charges.

Professional and management fees

Certification

Specialist consultancy, including, but not limited to; Geotechnical, structural, pressure sewer, electricity, telecommunications, bushfire, ecological or other specialist services.

Any building &/or amenity construction

Future planning consultancy, Development Applications and/or approval modifications etc.

Additional works as a result of Force Majeure or other unforeseen circumstances.