

## REQUEST FOR QUOTE (RFQ) – STORMWATER DRAINAGE PACKAGE

**Project:** Limestone Creek Estate Development – Yeppoon

**Project No.:** 5614

**Principal Contractor:** McIntosh Civil

**Date:** 07-14-2026

**Attention:** To Whom It May Concern

McIntosh Civil invites quotations from suitably qualified civil contractors for the **Stormwater Drainage Package** associated with the **Limestone Creek Estate Development, Yeppoon QLD**.

The works are to be undertaken in accordance with the Land Dynamics Australia engineering drawings, Livingstone Shire Council requirements, Capricorn Municipal Development Guidelines (CMDG), structural engineering details and applicable Australian Standards.

## SCOPE OF WORKS – STORMWATER DRAINAGE

Provide all labour, plant, materials, equipment, supervision and incidentals necessary to complete the stormwater drainage, interlot drainage, culvert works, subsoil drainage and bio-retention infrastructure associated with the development.

## STORMWATER DRAINAGE WORKS

### Western Trunk Road

Supply, excavate, bed, lay, joint and backfill stormwater infrastructure including compaction testing and all associated works:

#### Pipework

- 34.8m of 375mm HDPE pipe.
- 58.3m of 675mm Class 3 RRJ RCP.
- 17.3m of 750mm Class 3 RRJ RCP.
- 235.2m of 3.6m x 0.9m RCBC.
- 33.6m of 3.6m x 1.2m RCBC.

#### Pits

- 2 No. CMDG Type A SAG pits.
- 1 No. CMDG Type A Gully Pit.
- 3 No. custom pits.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

## Culvert Structures

- Headwalls to suit 375mm HDPE and 750mm RCP systems.
- 1,072m<sup>2</sup> culvert base slab construction.
- 2 No. cast in-situ culvert headwalls including aprons.
- Outlet protection and scour protection works.

## Stages 1 & 2 Stormwater Drainage

### Pipework

- 584.5m of 375mm HDPE.
- 163.5m of 450mm HDPE.
- 311.4m of 525mm HDPE.
- 309.0m of 600mm HDPE.
- 34.4m of 675mm RCP.
- 19.9m of 750mm RCP.
- 37.6m of 825mm RCP.
- 117.9m of 900mm RCP.

### Pits

- 7 No. SAG pits.
- 53 No. standard gully pits.
- 7 No. custom grated junction pits.

### Headwalls

- Headwall to twin 900mm RCP.
- Temporary headwalls to 600mm and 375mm systems.
- Outlet protection works.

## Stages 3, 4, 5 & 6 Stormwater Drainage

### Pipework

- 465.8m of 375mm HDPE.
- 177.6m of 450mm HDPE.
- 44.7m of 525mm HDPE.
- 204.0m of 600mm HDPE.
- 252.5m of 750mm RCP.



### Pits

- 6 No. SAG pits.
- 30 No. standard gully pits.
- 7 No. custom grated junction pits.

### Headwalls

- Headwalls to 750mm RCP systems.
- Headwall to 525mm HDPE outlet.
- Removal of temporary Stage 1 & 2 headwalls.
- Outlet protection works.

## INTERLOT DRAINAGE

### Stages 1 & 2

Provide all interlot drainage including:

- 126m of 150mm uPVC.
- 123m of 200mm uPVC.
- 134m of 225mm uPVC.
- 250m of 300mm uPVC.
- 26 junction connections.
- 44 kerb adaptors.
- 264m of lot connection pipework.
- 26 precast inspection pits.

### Stages 3, 4, 5 & 6

Provide all interlot drainage including:

- 45m of 150mm uPVC.
- 40m of 200mm uPVC.
- 325m of 225mm uPVC.
- 55m of 300mm uPVC.
- 25 junction connections.
- 39 kerb adaptors.
- 234m of lot connection pipework.
- 25 precast inspection pits.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

### SUBSOIL DRAINAGE

Provide complete subsoil drainage systems including:

- 100mm draincoil with filter sock.
- Flushing points at required intervals.
- Approximately 2,346m of subsoil drainage to Stages 3–6.

### BIO-RETENTION BASINS

#### South Bio-Retention Basin

Construction of complete bio-retention system including:

- 436m<sup>2</sup> filtration layer.
- 436m<sup>2</sup> transition layer.
- 436m<sup>2</sup> aggregate drainage layer.
- Drainage pipework, flushing points, low flow pit and outlet structure.

#### Northern Bio-Retention Basin

Construction of complete basin system and outlet works.

#### Western Bio-Retention Basin

Construction of complete basin system and outlet works.

### DRAWING REFERENCES

Please base your quotation on the following documentation:

- 5614-1000 – Cover Sheet & Drawing Index.
- 5614-1001 – Overall Layout Plan.
- 5614-1002 to 1005 – General Layout Plans.
- Stormwater drainage layouts.
- Longitudinal sections.
- Culvert drawings.
- Headwall details.
- Bio-retention basin details.
- Structural drawings associated with stormwater infrastructure.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

### INCLUSIONS

Your price shall include:

- Excavation and trench support.
- Supply and installation of all pipes.
- Bedding, embedment and backfilling.
- Compaction testing coordination.
- Concrete pits and structures.
- Headwalls and outlet structures.
- RCBC installation.
- Culvert slab construction.
- Junctions and kerb adaptor systems.
- Interlot drainage.
- Subsoil drainage.
- Bio-retention basin construction.
- QA documentation.
- As-constructed information.
- Testing and commissioning.
- Protection of completed works.
- Final cleanup.

### SUBMISSION REQUIREMENTS

Please provide:

- Lump Sum price for the complete package.
- Schedule of rates for all pipe classes and diameters.
- Rates for pits, headwalls and RCBC installation.
- Rates for interlot drainage and kerb adaptors.
- Rates for bio-retention basin construction.
- Programme duration.
- Earliest commencement availability.
- Assumptions and exclusions.
- Proposed methodology.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670



## SUBMISSION INSTRUCTIONS

### Ben McIntosh

 [ben@mcintoshcivil.au](mailto:ben@mcintoshcivil.au)

 0411 894 191

### Chris Abad – Estimating Support

 [chris@mcintoshcivil.au](mailto:chris@mcintoshcivil.au)

### Email Subject:

**RFQ – Stormwater Drainage Package – Limestone Creek Estate Yeppoon**

Kind Regards,

**McIntosh Civil**

**Tendering & Procurement Team**



07 4152 9971



[admin@mcintoshcivil.au](mailto:admin@mcintoshcivil.au)



[www.mcintoshcivil.au](http://www.mcintoshcivil.au)



18 Ellen Drive, Thabeban, Q, 4670