

REQUEST FOR QUOTE (RFQ) – POTABLE WATER RETICULATION PACKAGE

Project: Limestone Creek Estate Development – Yeppoon

Project No.: 5614

Date: 07-14-2026

Attention: To Whom It May Concern

McIntosh Civil invites quotations from suitably qualified civil contractors for the **Potable Water Reticulation Package** associated with the **Limestone Creek Estate Development, Yeppoon QLD**.

The works are to be completed in accordance with the Land Dynamics Australia engineering drawings, Livingstone Shire Council requirements, Capricorn Municipal Development Guidelines (CMDG), SEQ Water standards where applicable, relevant Australian Standards, and project specifications.

SCOPE OF WORKS – WATER RETICULATION

Provide all labour, plant, materials, equipment, supervision, testing and incidentals necessary to complete the potable water reticulation works for the development.

The works generally comprise supply, excavation, bedding, installation, jointing, thrust restraint, backfilling, testing and commissioning of potable water infrastructure including pipelines, hydrants, valves, fittings and property services.

WESTERN TRUNK ROAD WATER RETICULATION

Watermain Installation

Supply, excavate, bed, lay, joint and backfill:

- 471m of 250mm PVC PN16 potable watermain.

Hydrants

Supply and install:

- 4 No. hydrants to suit 250mm main.
- 1 No. temporary ducksfoot hydrant to suit 250mm main.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

Valves

Supply and install:

- 3 No. stop valves to suit 250mm main.
- 1 No. scour valve to suit 250mm main.

Fittings

Supply and install all bends, tees and thrust blocks including:

- 250mm bends ranging from 6° to 90°.
- 250mm x 250mm tee.

Testing & Commissioning

- Pressure testing.
- Watermain disinfection by Council (provisional).
- Council connection works (provisional).

STAGES 1 & 2 WATER RETICULATION

Main Network

Supply, excavate, bed, lay, joint and backfill:

- 83m DN63 PE100 PN12.5 watermain.
- 630m of 100mm PVC PN16 watermain.
- 322m of 200mm PVC PN16 watermain.
- 976m of 250mm PVC PN16 trunk watermain.

Hydrants

Supply and install:

- 9 hydrants to suit 100mm mains.
- 3 hydrants to suit 200mm mains.
- 13 hydrants to suit 250mm mains.
- 6 temporary ducksfoot hydrants.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

Valves

Supply and install:

- 10 stop valves to suit 100mm mains.
- 5 stop valves to suit 200mm mains.
- 6 stop valves to suit 250mm mains.
- 1 scour valve complete with connection to drainage infrastructure.

Property Services

Provide complete property service connections including:

- Main cocks and tapping bands.
- Service conduits under road crossings.
- Short-side services.
- Poly pipe and fittings.
- Valve boxes and covers.

Service Quantities

- 56 property service connections from potable mains.
- 27 road crossing services.
- 40 short-side services.

Fittings

Supply and install all tees, reducers, bends, connectors, end caps, tapping bands and thrust blocks required to complete the network.

ROAD 1 MAIN COLLECTOR WATER RETICULATION

Supply and install:

- 38m of 100mm PVC PN16 watermain.
- 400m of 250mm PVC PN16 watermain.
- Hydrants, valves, tees, bends and thrust blocks as detailed within the BOQ.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

Provide:

- 13 property service connections.
- 3 water services under road crossings.
- 10 short-side water services.

LEAD-IN WATERMAIN (PROVISIONAL)

Provide provisional pricing for:

- 402m of 250mm PVC PN16 watermain connecting to Adelaide Park Road.
- Hydrants and valve installations.
- Connection to existing Council infrastructure.
- Pressure testing and commissioning.

STAGES 3, 4, 5 & 6 WATER RETICULATION

Watermain Installation

Supply, excavate, bed, lay, joint and backfill:

- 80m DN63 PE100 PN12.5 watermain.
- 108m DN63 PE100 PN12.5 watermain.
- 693m of 100mm PVC PN16 watermain.

Hydrants & Valves

Supply and install:

- 10 hydrants to suit 100mm mains.
- 3 stop valves to suit 100mm mains.

Property Services

Provide:

- 28 property service connections.
- 13 water services under roads.
- 11 short-side services.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

Temporary Works

- Remove and dispose of temporary ducksfoot hydrants installed during Stages 1 & 2.

DRAWING REFERENCES

Please base your quotation on the following documentation:

- 5614-1000 – Cover Sheet & Drawing Index.
- 5614-1001 – Overall Layout Plan.
- 5614-1002 to 1005 – General Layout Plans.
- Water Reticulation Layout Drawings.
- Watermain Long Sections.
- CMDG Standard Water Details.
- Hydrant and Valve Schedules.
- Water Service Connection Details.
- Watermain Subcontractors.xlsx.

INCLUSIONS

Your quotation shall include:

- Mobilisation and demobilisation.
- Excavation and trench support.
- Bedding, embedment and backfilling.
- Supply and installation of all watermains.
- All valves, hydrants, tees, reducers and fittings.
- Thrust blocks and concrete encasement where required.
- Marker tape and identification systems.
- Property service connections.
- Road crossing services.
- Pressure testing.
- Coordination of disinfection requirements.
- Practical completion testing.
- Quality assurance documentation.
- As-constructed information.
- Protection of completed works.
- Site cleanup and disposal of surplus materials.



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670

SUBMISSION REQUIREMENTS

Please provide:

- Lump Sum Price for the complete package.
- Schedule of Rates for:
 - DN63 PE100 watermain (\$/m).
 - 100mm PVC PN16 watermain (\$/m).
 - 200mm PVC PN16 watermain (\$/m).
 - 250mm PVC PN16 watermain (\$/m).
 - Hydrants (\$/No.).
 - Valves (\$/No.).
 - Property services (\$/No.).
 - Road crossing water services (\$/No.).
 - Pressure testing (\$/item).
- Earliest commencement date.
- Construction programme.
- Proposed methodology.
- Key project personnel.
- Assumptions and exclusions.
- Quote validity period.

SUBMISSION INSTRUCTIONS

Ben McIntosh

 ben@mcintoshcivil.au

 0411 894 191

Chris Abad – Estimating Support

 chris@mcintoshcivil.au

Email Subject:

RFQ – Water Reticulation Package – Limestone Creek Estate Yeppoon

We appreciate your interest and look forward to receiving your quotation.

Kind Regards,

McIntosh Civil

Tendering & Procurement Team



07 4152 9971



admin@mcintoshcivil.au



www.mcintoshcivil.au



18 Ellen Drive, Thabeban, Q, 4670